



MEMBRANE TIE-IN TO SHINGLE ROOF SYSTEM

NOTES:

1. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURERS SPECIFICATIONS.
2. DO NOT SCALE DRAWINGS.
3. MIN. SLOPE 1/4":12" AWAY FROM STRUCTURE.
4. PLYWOOD SUBSTRATES TO BE EXTERIOR GRADE MIN. 5/8" T&G OR ALTERNATIVELY MIN. 5/8" WITH ALL PLYWOOD JOINTS BLOCKED FROM BELOW.
5. AS A SUPPLIER OF MATERIALS ONLY, SKYLINE BUILDING SYSTEMS INC. DOES NOT ASSUME RESPONSIBILITY FOR ERRORS IN DESIGN, ENGINEERING, QUANTITIES, OR DIMENSIONS. THE ARCHITECT, CONTRACTORS, OR OWNERS REPRESENTATIVE MUST VERIFY ALL DIMENSIONS, SIZES AND SUITABILITY OF DETAILS.